

15-165-19036-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 27 Twp. 18S Rge. 20 XEX (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Sunray DX Oil Company
Lease Name Lucille Beyers Well No. 1
Office Address P. O. Box 729, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-24 1964
Application for plugging filed 12-24 1964
Application for plugging approved 12-24 1964
Plugging commenced 12-24 1964
Plugging completed 12-24 1964
Reason for abandonment of well or producing formation
No commercial oil found

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4183 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				* 8-5/8"	336'	None
				* Set at	345'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Set cement plugs at 540 ft. with 25 sacks, 300 ft. with 25 sacks, and at 40 ft. with 25 sacks. Cemented with 15 additional sacks in top of 8-5/8" casing after cement settled. Cemented to top of surface casing. All intervals between cement plugs and to total depth filled with 9.9# mud laden fluid.

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1965
1-4-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stickle Drilling Company
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
C. M. GRAHAM (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. M. Graham, Acting District Manager
P. O. Box 729, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1964

My commission expires February 22, 1967

D. L. Jackson Notary Public

Sunray DX Oil Company
Tulsa, Oklahoma

30 December 1964
Wichita, Kansas

Drig. Contractor: Stickle Drilling Co.
Date Commenced : 14 December 1964
Date Completed : 24 December 1964

Lucile Beyer No. 1
NE NE NE 27-18S-20W
Rush County, Kansas

DRILLERS LOG

Depth figures indicate base of formation:

Post rock	90
Shale & gumbo	347
Red bed, sand & shale	731
Red bed & shale	1360
Shale & shells	1530
Anhydrite	1560
Shale & shells	1990
Shale & lime	2133
Lime & shale	2420
Lime	2724
Lime & shale	2820
Shale & lime	3605
Lime	4080
Sand	4107
Conglomerate	4133
Mississippi chat	4158
Chert Mississippi	4172 TD

I, R.B. Parriott, hereby certify that to the best of my knowledge & belief, the above is a true & complete Drillers log of the Sunray DX Oil Companys No. 1 Lucile Beyer well, NE NE NE 27-18S-20W Rush County, Kansas.


R.B. Parriott


Wanda J. Steakley, Notary Public

My Commission Expires 16 January 1966.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1965

CONSERVATION DIVISION
Wichita, Kansas