

15-165-00315-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rush County. Sec. 33 Twp. 17 Rge. 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C W/2 NW NE  
Lease Owner Morrison Producing Co.  
Lease Name Wagner Well No. 1  
Office Address Box 712, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed Feb. 13 1962  
Application for plugging filed Feb. 13 1962  
Application for plugging approved Feb. 13 1962  
Plugging commenced Feb. 13 1962  
Plugging completed Feb. 13 1962  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3592 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1106'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug @ 480' w/20 sax cement  
Middle " @ 180' w/20 sax cement  
Top plug @ 35' w/10 sax cement

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1962  
2-16-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Woodman & Iannitti Drilling Co.  
Address 714 Union Nat'l. Bldg., Wichita 2, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman  
714 Union Nat'l. Bldg.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 1962

My commission expires Oct. 10, 1963  
Francis A. Solomon Notary Public.



D R I L L I N G L O G

Company: Morrison Producing Company  
 Lease: #1 Wagner C W/2 NW NE 33-17-17W, Rush County, Kansas  
 Contractor: Woodman & Iannitti Drilling Company  
 Date Commenced: 2-2-62  
 Date Completed: 2-13-62  
 Total Depth: 3592'  
 Casing: 8 5/8" @ 1106' with 500 sacks cement

Figures Indicate the Bottom of Formation

0 - 60 Surface Clay & Shale  
 70 Post Rock  
 100 Shale  
 130 Sand & Shale  
 240 Shale  
 470 Red Bed & Shale  
 540 Shale & Streak of Sand  
 750 Sand  
 865 Shale & Red Bed  
 1090 Red Bed  
 1120 Anhydrite  
 1400 Red Bed, Shale & Shells  
 1890 Shale & Shells  
 1990 Lime  
 2185 Lime & Shells  
 2680 Lime  
 2975 Shale & Lime  
 3565 Lime  
 3583 Lime  
 3592 Lime

RECEIVED  
 STATE OF KANSAS COMMISSION

FEB 13 1962

2-16-62

CONSERVATION DIVISION  
 Wichita, Kansas

I certify the above to be a true and correct copy of the Driller's Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

By: X. T. Woodman