

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Summer County. Sec. 26 Twp. 31 Rge. 3 ~~4S~~ W (W)

Location as "NE/CNWxSWx" or footage from lines S/2 NW NE

Lease Owner Beardmore Drilling Company

Lease Name Hartman Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced 3-15-66 _____ 19__

Plugging completed 3-16-66 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3520 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	350'	None
				5-1/2"	2120'	1726'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 2060' and dumped 5 sacks of cement @ ~~2060'~~ 2060' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 267' to 257' and dumped 20 sacks of cement. Mudded hole to 35', set rock bridge to 25' and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1966

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1966

Milton J. Volin
Notary Public.

WELL LOG - Hartman # 1

26-31-3W

OPERATOR: Beardmore Drilling Company
700 One Twenty Building
Wichita, Kansas 67202

LOCATION: S/2-NW-NE
26-31S-3W
Sumner County,
Kansas

CONTRACTOR: German Drilling Company
502 Petroleum Building
Wichita, Kansas 67202

Farm: Hartman
Date Commenced: 12-15-65
Date Completed: 12-31-65

Well No. 1

From	To	Formation
0	191	Clay Sand Red Bed
191	2066	Red Rock
216	475	Shale
475	580	Shale & Shells
580	795	Anhydrite & Lime
795	1040	Anhydrite & Lime
1040	1180	Lime & Shale
1180	1445	Shale & Lime Shells
1445	1785	Shale & Lime
1785	1895	Shale & Lime
1895	1928	Lime
1928	1950	Shale & Lime
1950	2000	Shale & Lime
2000	2059	Lime
2059	2075	Core # 1
2075	2085	Sand
2085	2150	Lime & Shale
2150	2305	Lime & Shale
2305	2410	Lime & Shale
2410	2610	Sandy shale & shells
2801	2905	Shale & Lime
2905	2935	Shale & Lime
2935	3080	Shale
3282	3312	Lime
3312	3375	Lime
3375	3397	Lime
3397	3425	Shale & Lime
3425	3460	Lime & Shale
3460	3520	TD Lime & Shale
3520	TD	

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the foregoing is a true and correct copy of the Well log for the Hartman # 1, drilled for Beardmore Drilling Company and completed December 31, 1965.

GERMAN DRILLING COMPANY

Harvey F. German
Harvey F. German-Owner

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

Subscribed and sworn to, before the undersigned, a Notary Public, in and for County and State aforesaid, this fourth day of January, 1966.

Geneva M. German
Geneva M. German-Notary Public

My Commission expires February 28, 1968