

K-165-02229-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 2 TWP. 17 SRGE. 17 W E/W
Location as in quarters or footage from lines:
NW SW SW

*			

Lease Owner Frontier Oil Company.
Lease Name Steitz-Decker Well No. 2
Office Address 1720 Kansas State Bank Bldg., Wichita Ks.
Character of Well (Completed as Oil, Gas or Dry Hole): Gas Well.
Date Well Completed 07-25-62
Application for plugging filed 06-17-82
Plugging commenced 06-22-82
Plugging completed 06-22-82
Reason for abandonment of well or producing formation Gas depleted.

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Marion Schmidt.
Producing formation Topeka Depth to top 3098 bottom 3332 T.D. 3672'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		Top	220'	8-5/8"	07-25-62	Still in hole.
		Top	3230'	4 1/2"	07-25-62	Still in hole.
Stage Collar Set in	Anhydrite w/550 sx Cmt					

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. The following plugging materials used, from bottom to top:

<u>50 sx cmt, 50/50 Poz, 4% Gel, 3% CC w/2 sx hulls -</u>	<u>to bottom in formation</u>
<u>10 sx Gel</u>	<u>Apx. 2984</u>
<u>1 sx hulls</u>	<u>Apx. 2984-2804</u>
<u>8 sx gel</u>	<u>Apx. 2804-1364</u>
<u>1 4 1/2" Plug</u>	<u>1364</u>
<u>100 sx 50-50 Poz, 4% Gel, 3% CC</u>	<u>1364-Surface</u>

(Calculations by displacement)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Company, Box 31, Russell, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss.

George A. Angle (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature)

George A. Angle
1720 Ks St Bank Bldg., Wichita, Ks
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1982



My Commission expires: 5-14-85

Jean Stocks
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1982

CONSERVATION DIVISION
Wichita, Kansas

