

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rush

County. Sec. 34 Twp. 17 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Aylward Drilling Company

Lease Name Lohrey "B"

Well No. 1

Office Address 813 1st National Bank Bldg. - Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 20 1960

Application for plugging filed March 20 1960

Application for plugging approved March 21 1960


Plugging commenced March 21 1960

Plugging completed March 21 1960

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3582 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1097'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3582 to 400'
Set Halliburton plug at 400 with 1 1/3 sacks hulls and 10 sacks cement. Cement 400 to 350, heavy mud 350 to 180.
Halliburton plug at 180 with 1/3 sack hulls and 10 sacks cement. Cement 180 to 130. Heavy mud 130 to 40.
Halliburton plug at 40 with 1/3 sack hulls and 5 sacks cement. Cement 40' to surface.

RECEIVED
COMMISSION
4-21-60
APR 21 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 1st National Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Charles D. Williams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams
813 1st Nat'l Bank Bldg. - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1960

My commission expires Dec. 11, 1961
Duane Jessup Notary Public.

LOHREY "B" NO. 1

Casing Record: 8 5/8" - 1097'
 Company: Aylward Drilling Company
 Contractors: Aylward Drilling Company
 Location: SE SE NE 34-17-17W
 Rush County
 Kansas
 Commenced: March 9, 1960
 Completed: March 21, 1960
 Elevation: 2013 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay & Shale	0	350	Set 8 5/8" surface pipe @ 1097' w/325 sacks cement.
Sand, Shale & Shells	350	490	
Sand	490	620	Geological Tops:
Shale, Shells & Red Bed	620	760	
Red Bed & Shale	760	1042	
Sandstone	1042	1070	
Red Bed & Shale	1070	1092	
Anhydrite	1092	1117	
Shale & Shells	1117	1650	
Shale & Lime	1650	1900	
Shale w/Lime	1900	2035	
Broken Lime	2035	2170	
Lime	2170	2255	
Lime & Shale	2255	2355	
Broken Lime	2355	2440	
Shale & Lime	2440	2970	
Lime w/Shale Streaks	2970	2995	
Lime	2995	3251	DST 3525-70 Open 1 hr. Gas in 3 min. Gauge 1,190,000 CFG thruout test. Rec. 10" mud. IBHP 822#/20" - FBHP 790#/30". FP 185#-185#.
Lime & Shale	3251	3326	DST 3533-82 Open 1 hr. Gas in 2 min. Gauge 880,000 CFG. Rec. 125" mud. IBHP 760#/- FBHP 760#/30". FP 155#-185#. 20"
Lime	3326	3531	
Cong., Shale, Sand & Gran.Wsh.	3531	3570	
Granite	3570	3582 T.D.	

D & A

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 22nd day of March, 1960

Duane J. Gessen
Notary Public

My commission expires December 11, 1961

RECEIVED
 CORPORATION COMMISSION
 APR 21 1960
 CONSERVATION DIVISION
 Wichita, Kansas