

15-165-20394-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Section Plot grid with 4 columns and 4 rows.

Locate well correctly on above Section Plot

Rush County, Sec 16 Twp 17S Rge 17 (E) (W)
Location as "NE/CNWSW" or footage from lines SE NE SE
Lease Owner Frontier Oil Company
Lease Name Foos B#1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/18/73 19
Plugging completed 11/6/73 19
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 8-5/8, 211, none. Row 2: 4 1/2", 3598, 1606.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom to 3590', pushed plug to 3000' and ran 20' sand and 3 sacks cement. Shot pipe at 2629', 2535', 2440', 2311', 2205', 2118', lost wire line and had to fish out of hole. Pipe stuck, had to shot again, shot at 1501', pulled pipe. Pumped 3 sacks hulls, 20 sacks gel and 120 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PLUGGING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, KS.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 12th day of November 1973

[Signature]
Notary Public.

My commission expires



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

K-165-20394-0000

DRILLERS LOG

No. 1 Foos "B"

CASING RECORD:

8 5/8" @ 211'
w/135 sx cement

4 1/2" @ 3598'
w/275 sx cement

TOTAL DEPTH: 3600'

COMPANY: Frontier Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: May 13, 1971

COMPLETED: May 24, 1971

DESCRIPTION:

SE NE SE
16-17S-17W
Rush County,
Kansas

ELEVATION: 2080' GL
2085' RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface hole	0	212	
Shale Gray	212	370	
Shale	370	480	
Hard Rock	480	484	
Shale	484	585	
Sand	585	800	
Shale & Shells	800	1166	
Anhydrite	1166	1203	
Shale & Shells	1203	1670	
Shale & Lime	1670	2188	
Lime	2188	2575	
Lime & Shale	2575	2812	
Tarkio	2812	2875	
Lime & Shale	2875	3056	
Lime	3056	3292	
Hebner	3292	3296	
Lime & Shale	3296	3346	
LKC	3346	3360	
Lime	3360	3565	
Conglomerats & Shale	3565	3586	
Quartz	3586	3600	


RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 26th day of May, 1971.



Virginia K. Albert
Notary Public

July 23, 1974