

15-1105-35223-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rush County. Sec. 22 Twp. 17 Rge. (E) 17(W)

Location as "NE/CNW%SW%" or footage from lines SW NE NE

Lease Owner Morrison Drilling Company, Inc.

Lease Name Foos Well No. 1

Office Address Drawer 712, El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 3, 1954

Application for plugging filed Verbal March 4, 1954

Application for plugging approved Verbal March 4, 1954

Plugging commenced March 4, 1954

Plugging completed March 4, 1954

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Horner, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3608 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to 300' of top. Put in 1/3rd sack of cottonseed hulls. Pushed plug down to 300'. Cemented through drill pipe with 20 sacks of mixed cement. Filled hole 35' of top. Put in 1/3rd sack of cottonseed hulls. Push plug down and cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morrison Drilling Company, Inc.

Address Drawer 712, El Dorado, Kansas

STATE OF KANSAS COUNTY OF BUTLER
C. W. Wilson (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Drawer 712, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March 1954

My commission expires January 10, 1955

Notary Public.

24-7366-S 3-53-20M

3-9-54

PLUGGING
FILE sec 22 T 17 R 17 W
BOOK PAGE 18 LINE 2

WELL LOG - FOOS #1

Operator: Morrison Drilling Company, Inc.,
 Drawer 712,
 El Dorado, Kansas

LOCATION: SW NE NE
 Section 22-17-17W
 Rush County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.,
 Drawer 712, El Dorado, Kansas

PRODUCTION: D & A

Farm: Foos Well No. 1 Field: Reichel

Date Commenced: February 16, 1954
 Date Completed: March 3, 1954

Elevation: 2068 DF
 2066 Gr

Total Depth: 3608 - rotary

<u>From</u>	<u>To</u>	<u>Formation</u>
0	40	Soil and Surface Clay
40	400	Shale and Shells
400	775	Slale and Sand
775	840	Shale, Line & Red Bed Streaks
840	1125	Shale and Shells
1125	1154	Shale and Sald
1154	1159	Anhydrite
1159	1420	Red Bed, Shale & Shells
1420	1655	Shale and Shells
1655	1820	Salt
1820	1868	Lime and Shale
1868	2412	Lime
2412	2430	Lime and Shale
2430	2516	Broken Lime
2516	2662	Lime and Shale
2662	2960	Shale and Line Streaks
2960	3010	Lime and Shale
3010	3044	Sandy Shale
3044	3278	Topeka Lime
3278	3298	Heebner Shale
3298	3330	Dodge Lime
3330	3567	Kansas City Lime
3567	3575	Red Shale
3575	3582	Granite Wash
3582	3608	Granite Wash
3608		Total Depth

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Foos #1 well drilled for Morrison Drilling Company, Inc., and completed March 3, 1954.

MORRISON DRILLING COMPANY, INC.



C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
)
 COUNTY OF BUTLER)

ss:

SUBSCRIBED AND SWORN TO, Before me, the undersigned, a Notary Public, in and for the County and State aforesaid this 8th day of March, 1954.



Notary Public

My Commission Expires January 10, 1955.

3-9-54

PLUGGING
 FILE SEC 22-17-17W
 BOOK PAGE 18 LINE 2