

15-165-19020-0000

LEASE NAME Kleweno "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION SW - NE

SEC. 16 TWP. 17 S. RGE. 17 (E) or (W)

COUNTY Rush

Date Well Completed 5-25-63

Plugging Commenced 10-2-91

Plugging Completed 10-2-91

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached?

Producing formation L-KC Top Depth to top 3064' bottom 3438' T.D. 2820'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Gas & Water	3392'	3438'	8 5/8"	212'	None
Topeka	Gas & Water	3064'	3073'	4 1/2"	3598'	None

RECEIVED
STATE CORPORATION COMMISSION
10-8-91
OCT 08 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran tubing to 2800'. Spotted 50 sx. 60/40 Poz, 6% gel. Pulled 25 jts. to 2000'. Spotted 50 sx. 60.40 poz, 6% gel. Pulled 25 jts to 1200'. Pumped 110 sx. 60/40 Poz, 6% gel & circulated cement. Laid down tubing. Hooked to 4 1/2" casing. Squeezed in 15 sx. of same. Pressured to 700#. SIP - 500#. Hooked to 8 5/8" pressured to 300#. 5 sxs. in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No.

Address Russell, KS

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1991

Pamela L. Steckel
Notary Public



My Commission expires: 11-19-92