

15-055-30068-
E000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Finney County, Sec. 36 Twp. 21S Rge. (E)34 (W)

Location as "NE/CNW&SW&" or footage from lines 150' S. of NW SE
Lease Owner Wm Gruenerwald and Associates, Incorporated
Lease Name Maune Well No. 1
Office Address P. O. Box 909, Colorado Springs, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 24 19 66
Application for plugging filed December 24 19 66
Application for plugging approved December 24 19 66
Plugging commenced December 24 19 66
Plugging completed December 24 19 66
Reason for abandonment of well or producing formation No producible shows

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes
Edgar J. Eves

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	425'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Used pump truck.
Heavy mud to 475', added 35 sacks cement through drill pipe;
heavy mud to 40', pushed wooden plug and built bridge with 1/2 sack hulls, added 15 sacks cement. Job complete 5 AM, 12-24-66.

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Sam N. Stephens (employee of owner) or ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sam N. Stephens
Garvey Drilling Company, Route 2, Great Bend, Kan.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 66
Richard Stoyes
Notary Public.

My commission expires November 5th, 1969

WELL LOG

COMPANY Wm Gruenerwald and Associates, Incorporated

SEC. 36 T. 21S R. 34W

FARM Maune NO. 1


LOC. 150' S. of NW SE

TOTAL DEPTH 4922'

COUNTY Finney

COMM. 12-8-66 COMP. 12-24-66

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 425' w/300 sx

ELEVATION 2916' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

426' Top Soil, Sand, Blue Shale and Shells
825' Shale and Shells
1342' Shale, Sand and Red Bed
1360' Anhydrite
2015' Shale and Shells
2035' Anhydrite
2540' Shale with Lime
3100' Lime and Shale
3270' Lime
3315' Lime, Shale, and Chalk
3622' Lime and Shale
4016' Lime
4095' Lime and Shale
4922' Lime
4922' RTD

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1967
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Maune No. 1 well.

Sam N. Stephens

Subscribed and sworn to before me this 29th day of December 1966

My Commission Expires: November 5th, 1969

Richard D. Doy
NOTARY PUBLIC