


WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Finney County. Sec. 16 Twp. 21S Rge. 33W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Hyer Well No. 4
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 9, 1960
Application for plugging filed May 9, 1960
Application for plugging approved May 9, 1960
Plugging commenced May 9, 1960
Plugging completed May 9, 1960
Reason for abandonment of well or producing formation No commercial quantities of oil found.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4665 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	213'	Not Pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with 20 sacks of cement set at 550 feet; Second Plug at 200 feet with 20 sacks of cement; Top Plug at 40 feet with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor IMPERIAL OIL OF KANSAS, INC.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. J. Boone (employee of ~~owner~~ operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: K. J. Boone Pet. Engr.
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June, 1960
Mona L. Latier Notary Public.

My commission expires July 7, 1962

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1960
CONSERVATION DIVISION
Wichita, Kansas

Hyer No. 4
C NE SW Sec. 16-21S-33W
Finney County, Kansas

Total Depth: 4665'

Commenced: 4-23-60 Completed: 5-9-60

Elevation: 2885' K.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 213' with 175 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Clay and Sand	213'		
Shale	255'	Heebner	3776' (- 891)
Shale & Sand	1550'	Toronto	3789' (- 904)
Dakota sand	1750'	Lansing	3820' (- 935)
Shale & Redbed	1970'	Base/Kansas City	4270' (-1385)
Shells & Shale	2415'	Marmaton	4297' (-1412)
Shale & Lime	3150'	Cherokee shale	4441' (-1556)
Lime	3206'	Morrow shale	4579' (-1694)
Lime & Shale	3901'	Mississippian	4623' (-1738)
Lime	4665'	Rotary Total Depth	4665' (-1780)
Total Depth	4665'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: _____
K. J. Boone - Pet. Engr.

Subscribed and sworn to before me this 3rd day of June, 1960.

My Commission Expires:

July 7, 1962

Mona L. Latier

Mona L. Latier - Notary Public