

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

XC: dist 1.15-055-10151-0550  
JUN 7 1985

API NUMBER Nov. 1961

LEASE NAME Maune-Appleman

WELL NUMBER 3

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 21 RGE. 34 (X) or (W)

COUNTY Finney

Date Well Completed Dec. 1961

Plugging Commenced 6-14-90

Plugging Completed 6-22-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Petroleum Production Management, Inc.

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202

PHONE# (316) 265-4651 OPERATORS LICENSE NO. 6234

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. 1

Is ACO-1 filed? No If not, is well log attached? Yes - with CP-1

Producing Formation Miss. Depth to Top 4762 Bottom 4805 T.D. 4805

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Miss.	Oil	4762	4805	8-5/8	345	0
				5-1/2	4762	385

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran free point to T/rods @ 3125'. Shot off 2-3/8" @ 3124' & pull subs & T it. Pump 25 sx. Cl. H  
From 3088' to 2888'. Pull tbg. Csg. stuck @ 1000'. Shot off 5 1/2" @ 1200'. Pump 60 sx. Cl. H  
from 1190' to 995'. Shot off 5 1/2" @ 390'. Pump 55 sx. from 280'. Pump 10 sx. in top 8-5/8"  
Next day meas. T. cem. @ 340'. On 6-22-90 Pappas Concrete, Inc. Holcomb, KS. filled 8-5/8" to  
btm. of cellar. Cmt. held o.k.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service - Halliburton RECEIVED STATE CORPORATION COMMISSION

Address Garden City & Liberal, KS. JUN 26 1990

STATE OF Kansas COUNTY OF Sedgwick, ss.

(Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Park

(Address) 209 E. William, Suite 200  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 25th day of June, 19 90

Margaret A. Marx  
Notary Public

My Commission Expires: 3-1-92



# WELL LOG

COMPANY SHALLOW WATER REFINING COMPANY

SEC. 36 T.21S R. 34W

FARM MAUNE "B" NO. 1


LOG. C-NE, NE

TOTAL DEPTH 4805'

COUNTY FINNEY CO., KANSAS

COMM. November 2, 1961 COMP. November 19, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 345' w/250 sax.  
5 1/2" @ 4762' w/100 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Topsoil & sand
470	Shale
1326	Shale & sand
1345	Anhydrite
1407	Shale
1420	Anhydrite
1680	Shale & sand
1900	Shale
2345	Shale & shells
2545	Shale & lime
3000	Lime & shale
3065	Lime
3210	Shale & lime
3620	Lime & shale
3704	Lime
3865	Lime & shale
4082	Lime
4197	Chalky lime
4245	Lime
4310	Lime & chert
4650	Lime
4657	Shale
4805	Lime
4805	T. D.

State of KANSAS }  
County of BARTON }

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 MAUNE "B" well.

Verne A. Morris

Subscribed and sworn to before me this 28th day of November 19 61

My Commission Expires: November 12, 1962

Stanley  
NOTARY PUBLIC