

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Finney County, Sec. 30 Twp. 21 Rge. 34 N/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SW/4

Lease Owner Gas Producing Interprise
Lease Name Bretz Well No. 1

Office Address Box 1332, Amarillo, Texas 79189

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 7-13 1977

Application for plugging filed 4-10 1978

Application for plugging approved 4-14 1978


Plugging commenced 5-18 1978

Plugging completed 5-19 1978

Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes



Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Krider Depth to top 2915 Bottom 2985 Total Depth of Well 3120
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	Dolo & Anhy	2598	2632	8 5/8	490	None
Krider	Dolo & Anhy	2632	2680	4 1/2	3046	1510
Winfield	Polo & SD	2680	2742			
Council Grove	Limestone	2908	3087			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pump 25 sks. of cement from 2885 to 2635

Pump 50 sks. of cement from 100 to 300

Put 10 sks. of cement from 10 to 0

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Ser. Box 506 Liberal, Kansas 67901 No. 511

STATE OF Texas COUNTY OF Potter, ss.
(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of June, 1978

[Signature]

Notary Public.

My commission expires July 19, 1979

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Bretz #1
 C-SW Sec 30-21S-34W
 Finney County Kansas

Commenced: 3-15-77

Completed: 3-20-77

OPERATOR: CIG Exploration, Inc.

Depth		Formation	Remarks
From	to		
0	75	Sand	Ran 14 jts of 24# 8 5/8" csg set @ 490' Cemented w/ 250 sks 35/65 Posmix 6% Gel 2% CC + 100 sks Class 3% CC PD @ 12:15 a.m. 3-16-77
75	500	Sand-Shale	
500	995	Shale	
995	2026	Shale-Sand	
2026	2400	Shale	
2400	2658	Shale-Lime	
2658	2996	Lime	
2996	3120	Lime-Shale	Ran 68 jts of 9 1/2# 4 1/2" csg set @ 3046' Cemented w/ 350 sks 35/65 Posmix 6% Gel 12 1/2# D-42 per Sack - 1/4# D-29 per sack + 150 sks 50/50 Posmix 18% Salt - 2% Gel - 1/4# D-29 PD @ 3:30 p.m. 3-20-77
	3120 - TD		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 22nd day of March, 1977.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

