

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Finney County. Sec. 19 Twp. 21 Rge. 34 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C SW/4

Lease Owner Gas Producing Interprise  
Lease Name Bretz Well No. 2  
Office Address Box 1332, Amarillo, Texas 79189  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole


Date Well completed 7-20 1977  
Application for plugging filed 4-10 1978  
Application for plugging approved 4-14 1978  
Plugging commenced 5-23 1978  
Plugging completed 5-25 1978

Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation Krider Depth to top 2625 Bottom 2639 Total Depth of Well 3100  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	Dolo & Anhy	2581	2617	8 5/8	503	None
Krider	Dolo & Anhy	2617	2666	1 1/2	3100	1512
Winfield	Dolo & SD	2666	2730			
Council Grove	Limestone	2898	3084			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 30 sks. of cement from 2870 to 2500

Pump 50 sks. of cement from 400 to 300

Put 10 sks. of cement from 10 to 0

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1978

Conservation Division  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Ser. Box 506 Liberal, Kansas 67901 No. 511

STATE OF Texas COUNTY OF Pottaw, ss.  
(employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of June, 1979

[Signature]

Notary Public.

My commission expires July 19, 1979

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Brentz #2  
 C-SW Sec 19-21S-34W  
 Finney County Kansas

Commenced: 3-24-77

Completed: 3-28-77

OPERATOR: CIG EXPLORATION, INC.

Depth		Formation	Remarks
From	To		
0	510	Shale	Ran 15 jts of 24# 8 5/8" csg set @ 501' Cemented w/ 250 sks 35/65 Posmix 6% Gel-2% CC +100 sks Class H 3% CC PD @ 5:30 p.m. 3-24-77
510	800	Redbed	
800	1380	Shale-Redbed	
1380	2307	Shale-Sand	
2307	2813	Shale-Lime	
2813	2944	Lime-Shale	
2944	3100	Lime	Ran 70 jts of 9 1/2# 4 1/2" csg set @ 3100' Cemented w/450 sks 35/65 Posmix 6% Gel 12 1/2# D42 per sack - 1/4# D-29 + 150 sks 50/50 Posmix 18% Salt 2% Gel - 1/4# D29 PD @ 7:00 p.m. 3-28-77
	3100 - TD		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' WELL Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 30th day of March, 1977.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

