

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,083-20109-000

LEASE NAME Gleason

WELL NUMBER "B" #3

1650 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 32 TWP. 23 RGE. 21 (E) or (W)

COUNTY Hodgeman

Date Well Completed _____

Plugging Commenced 4-29-88

Plugging Completed 5-6-88

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS Box 1303, Great Bend, Ks. 67530

PHONE# (918)-798-2607 OPERATORS LICENSE NO. 5123

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4577'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	262'	None
				5-1/2"	4571'	431.43'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 4250' and 5 sacks cement Shot casing at 3600', 2500', 1500', 1000', 800', 600' and 400'. Pulled 13 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls released plug and pumped 150 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

CONSERVATION DIVISION
Wichita, Kansas

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of May, 1988

My Commission Expires: _____
Iona M. Leatherman
Notary Public

