

15-055-10005-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Finney County, Sec. 14 Twp. 26S Rge. (E)32 (W)

Location as "NE/CNW&SW" or footage from lines C SE NE

Lease Owner Nathan Appleman and Earl F. Wakefield

Lease Name Ohmes Well No. 3

Office Address 515 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 5 1960

Application for plugging filed December 5 1960

Application for plugging approved December 5 1960

Plugging commenced December 5 1960

Plugging completed December 5 1960

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5261 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	850	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement plug thru drill pipe with 167 cubic feet Poz-mix 2900' up to 2600', Mud to 800', 25 sacks plug thru drill pipe at 800' up to 725', Mud to 35' below bottom of cellar cemented to bottom of cellar with 10 sacks, completed at 10:00 pm December 5, 1960

RECORDED
STATE CORPORATION COMMISSION
DEC 20 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl F. Wakefield (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Building, Wichita (Address)

SUBSCRIBED AND SWORN to before me this 17th day of December, 1960

My commission expires July 26, 1962 C. A. Snow Notary Public.

LEASE: OHMES #3
 OPERATOR: EARL F. WAKEFIELD
 CONTRACTOR: EARL F. WAKEFIELD
 COMM: 11/13/60 COMP: 12/6/60

LOCATION: C SE NE
 SECTION 14-26S-32W
 FINNEY COUNTY, KANSAS
 CASING: 8 5/8" Set at 850'

ELEVATION 2896 G.L.
 2907 K.B.

Surface Clay and Sand	140
Sand	455
Shale, Clay	555
Shale	850
Red Bed and Shale	1300
Anhydrite	1325
Red Bed and Sand	1800
Sand, Shale, Lime	1950
Lime	2125
Lime and Shale	2240
Shale, Lime	2450
Lime and Shale	2765
Lime	2857
Lime and Shells	2923
Lime	2993
Lime and Shale	3227
Lime	3448
Lime and Shale	3510
Lime	3832
Lime and Chalk	3905
Lime	3990
Lime and Shale	4064
Lime	4300
Lime with Shale	4357
Lime	4465
Lime with Shale	4500
Lime	4728
Lime and Chalk	4763
Lime	4970
Lime and Shale	5010
Lime, Shale	5036
Shale and Lime	5064
Lime with Shale	5091
Lime	5261
T. D.	5261

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the OHMES #3 well, located C SE NE Section 14-26S-32W, Finney County, Kansas.

EARL F. WAKEFIELD

By Earl F. Wakefield

Subscribed and sworn before me this 17th day of December, 1960.

C. A. Snow
 C. A. SNOW NOTARY PUBLIC

My commission expires July 26, 1962.