

15-165-00352-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County. Sec. 10 Twp. 18 Rge. (E) 20 (W)
Location as "NE/CNW&SW" or footage from lines C NW NE
Lease Owner A. L. Abercrombie, Inc.
Lease Name Williams Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed Sept. 24 19 63
Application for plugging filed Sept. 30 19 63
Application for plugging approved 19
Plugging commenced 5:00 a.m. Sept 24, 19 63
Plugging completed 8:00 a.m. Sept 24, 19 63
Reason for abandonment of well or producing formation dryhole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		0'	297'	8 5/8"	297'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 540' with 20 sacks cement, Plug @ 240' 1/4 sack hulls & 20 sacks cement. Top plug @ 35' 1/2 sack hulls and 10 sax cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1963

10-2-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Vaughan Drilling, Inc.
Address Box 825, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Wayne Dobbs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. VAUGHAN DRILLING, INC.

(Signature) Wayne Dobbs
BY WAYNE DOBBS, Vice-pres.

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 19 63

My commission expires Oct. 4, 1966

Kathryn M. Boxberger
Kathryn M. Boxberger Notary Public.

WELL LOG

COMPANY A. L. Abercrombie, Inc.
 CONTRACTOR Vaughan Drilling, Inc.
 FARM Williams #1
 LOCATION C NW NE of sec. 10-18-20W
 Rush County, Kansas
 ELEVATION 2145' K. B.
 SURFACE PIPE 8 5/8" cemented @ 297' with 175 sacks of posmix sunset.
 PRODUCTION D & A
 COMMENCED 9-11-63
 COMPLETED 9-24-63

<u>FORMATION</u>	<u>DEPTH</u>
Sandstone & Clay	20
Shale	297
Sandstone	370
Shale & Sandstone	635
Red Bed & Sand Streak	855
Dakota Sandstone	995
Red Bed & Shale	1370
Anhydrite	1417
Shale & Shells	1822
Shale	2120
Shale & Limestone	3370
Limestone & Chalk	3480
Limestone	3582
Limestone & Shale	3710
Limestone	4050
Sandstone & Shale	4090
Limestone & Shale (cherty)	4155
Limestone & Shale	4200

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 2 1963
 10-2-63
 CONSERVATION DIVISION
 Wichita, Kansas

FORMATION TOPS

Anhydrite	1370 (+ 775)
Heebner	3571 (-1426)
Toronto	3589 (-1444)
Kansas City	3615 (-1470)
Fort Scott	4000 (-1855)
Cherokee Shale	4044 (-1899)
Cherokee Sand	4058 (-1913)
Mississippi	4121 (-1976)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS

I, Donald D. Vaughan, of the VAUGHAN, DRILLING, INC., being first duly sworn on oath, state; that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

VAUGHAN DRILLING, INC.

BY Donald D. Vaughan
 DONALD D. VAUGHAN, PRES.

Subscribed and sworn to before me this 1st day of October, 1963.

My commission expires: Oct. 4, 1966

Kathryn M. Boxberger
 Kathryn M. Boxberger, Notary Public.