

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20427-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 8-24S-30W
660 feet from S Section Line, 4844 feet from E Section Line
Lease Name: O'BRATE-GRAY Well #: 2-8
County: GRAY Total Vertical Depth: 5000 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4824		WITH 2 SX CMT
PROD	4.5	4983	1384	WITH 150 SX CMT
SURF	8.625	452		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2013 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4824' WITH 4 SX CMT. PLUG AT 2010' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2013 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4824' WITH 2 SX CMT. SHOT CASING AT 2123'. PULL TO 2010' & PUMP 15 BBL GEL WATER & 50 SX CMT. START TO PULL CASING. RIG BROKE DOWN. CMT SET UP IN CASING WITH 30 SX CMT INSIDE & 20 SX CMT BEHIND THE 4 1/2" CASING. TAG TOC IN 4 1/2" @ 1500'. SHOOT COLLAR SPLIT SHOT @ 1384'. PIPE FREE. PULL TO 1208'. 1ST PLUG AT 1208' WITH 50 SX CMT. 2ND PLUG AT 484' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4874	4888		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

RECEIVED

APR 18 2013

KCC DODGE CITY

1917