

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20570-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 20-31S-40W
545 feet from S Section Line, 1840 feet from E Section Line
Lease Name: BROWN Well #: 3-1
County: MORTON Total Vertical Depth: 5100 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4850		WITH 2 SX CMT
PROD	5.5	5099	2375	WITH 175 SX CMT
SURF	8.625	1549		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2013 9:00 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: GEORGE RAYL Company: COPELAND Phone: _____

Proposed Plugging Method: SET CIBP @ 4850' & 2 SX CMT. PLUG AT 1580' WITH 20 SX GEL & 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2013 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PACKER LEFT IN HOLE AT 4900'. CIBP @ 4850' WITH 2 SX CMT. 1ST PLUG AT 1590' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4986	5022		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013


CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

APR 17 2013

KCC DODGE CITY