

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19528-00-01
Spot: SENWSWSW Sec/Twnshp/Rge: 18-32S-5E
955 feet from S Section Line, 4912 feet from E Section Line
Lease Name: BARNETT Well #: 3C
County: COWLEY Total Vertical Depth: 1993 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L.
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	1993	930	75 SX
PROD 7		2088		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2013 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/28/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 1930'. DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED PLUG @ 1900'. 3-12-2013, CUT CASING @ 930', LAYED DOWN 28 JOINTS 5-1/2" CASING. 3-15-2013, RIH W/TBG @ 300', COPELAND ACID SERVICE ESTABLISHED CIRCULATION AND MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL. 3-18-2013, RAN STRING LINE @ 300', DID NOT TAG CEMENT. 3-28-2013, RIH ON WIRELINE SHOT SQUEEZE HOLES @ 260'-261' (4 HOLES). RIH W/TBG @ 260', COPELAND ACID ESTABLISHED CIRCULATION & MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 3-28-2013. COPELAND ACID CEMENT TICKET #41816, & 41830. 3-29-2013, TOPPED WELL BACK TO SURFACE W/14 SXS, CLOSED PIT & LVELED BACK TO GRADE.

Perfs:

Top	Bot	Thru	Comments
1985	1990	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
APR 17 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLIANCE / 10 YR RULE/ DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
4/25/13
(TECHNICIAN)