

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20381-00-01
Spot: NWSESESW Sec/Twnshp/Rge: 31-10S-32W
642 feet from S Section Line, 3292 feet from E Section Line
Lease Name: HECKER A Well #: 1
County: THOMAS Total Vertical Depth: 4650 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4400		
DVT	5.5	2610		
PKR		4242		PACKER TYPE AND SETTING DEPTH: AR-1 GRIP SET @ 4242
PKR		4300		PACKER TYPE AND SETTING DEPTH: LOK-SET @ 4300'
PROD	5.5	4649		250 SX
SURF	8.625	261		175 SX
TI	2.375	4300		

Well Type: EOR UIC Docket No: E28155.2 Date/Time to Plug: 04/25/2013 9:30 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: RONALD VANROEKEL Company: D.G. HANSEN TRUST Phone: (785) 689-4816

Proposed Plugging Method: 8 5/8" surface pipe set at 261' w/175 sx cement. 5 1/2" production casing set at 4649' w/250 sx cement. DV tool set at 2610' w/550 sx cement. Perforations: 4612' - 4618', 4322' - 4326', 4268' - 4272', 4217' - 4220'. CIBP set at 4400'. TD4650'. PBTD 4308'. Ordered 450 sx 60/40 pozmix 4% gel cement, 11 sx gel and 550 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2013 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4250' and pumped 11 sx gel followed by 75 sx cement w/250 # hulls.
Pulled tubing to 2625' and pumped 130 sx cement w/200 # hulls.
Pulled tubing to 1300' and pumped 150 sx cement w/100 # hulls. Cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 30 sx cement.
Connected to 8 5/8" surface casing and pumped 40 sx cement. Maximum pressure 100 psi.

GPS: 39.13494N -100.93763W

Perfs:

Top	Bot	Thru	Comments
4217	4618		

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET # 39,351

Plugged through: TBG

District: 04

APR 26 2013

Signed

Darrel Dipman

cc to WIC 5/13/13 5/13/13

CM