

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23542-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 18-32S-5E  
2308 feet from S Section Line, 4258 feet from E Section Line  
Lease Name: BARNETT Well #: 5  
County: COWLEY Total Vertical Depth: 3088 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L.  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2360		
PROD	5.5	3088	660	75 SX
SURF	8.625	150		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2013 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/15/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK ON TOP OF PLUG @ 2300'. DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED PLUG @ 2237'. 2-27-2013, CUT CASING @ 660', LAYED DOWN 16 JOINTS 5-1/2" CASING. 3-15-2013, RIH W/TBG @ 300', COPELAND ACID SERVICE ESTABLISHED CIRCULATION AND MIXED & PUMPED 127 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 3-15-2013. COPELAND ACID CEMENT TICKET #41817. 3-28-2013, TOPPED WELL BACK TO SURFACE W/16 SXS, CLOSED PIT & LEVELED BACK TO GRADE.

Perfs:

Top	Bot	Thru	Comments
2350	2354	CSG	LAYTON

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 17 2013**

Remarks: COMPLIANCE/ 10 YR RULE/ DENIED TA

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: TBG

District: 02

Signed Duane Krueger  
3/15/13 (TECHNICIAN)