

6-14055 10151-0000

To: 1 051321
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 11/19/61

NE NE, SEC. 36, T 21 S, R 34 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Maune-Appleman Well # 3

Operator: Petroleum Production Management, Inc
Name & Address: 200 Sutton Place Bldg.
Wichita, KS 67202

County Finney 156.16

Well Total Depth 4805 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree License Number 6907

Address P.O. Box 458, Ness City, KS 67560

Company to plug at: Hour: 8 a.m. Day: 14 Month: 6 Year: 19 90

Plugging proposal received from Steve Park

(company name) Petroleum Production Management (phone) 316-265-4651

were: 5 1/2" at 4762' Open hole 4762-4805' Tubing stuck in hole

1st plug shoot tubing off at 3129' and dump 25 sx cement,

2nd plug shoot 5 1/2" casing at 1200', pump 60 sx cement down 5 1/2",

3rd plug displace 50 sx cement out of casing at 1200',

4th plug shoot casing at 390' and pump 55 sx cement,

5th plug pump 10 sx cement from 40-0'.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30 p.m. Day: 14 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug shot tubing off at 3129' and pumped 25 sx cement,

2nd plug shot 5 1/2" casing at 1200', pumped 60 sx cement down 5 1/2",

3rd plug displaced 50 sx cement out of casing at 1200',

4th plug shot casing at 390' and pumped 55 sx cement,

5th plug pumped 10 sx cement at 40-0', cement fell to 300'.

Filled surface pipe up with 4 yards readymix.

Remarks: Used Class H cement by Halliburton. Recovered 390' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-2-90

INV. NO. 28520

JUN 20 1990

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)