

1050295

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,237 0000

SW SE SE, SEC. 27, T 19 S, R 16 W
330 FSL feet from N corner of
990 FEL feet from W corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5770

Lease Name Karst Well # 1

Operator: Reif Oil Operations, Inc.

County Rush

Name & Address Box 298

Well Total Depth 3810 123.83 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1063 110

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Revlin Drilling, Inc. License Number 5671

Address Box 293, Russell, KS 67665

Company to plug at: Hour: 1:00 am Day: 25 Month: July Year: 19 84

Plugging proposal received from Duane Popp

(company name) Revlin (phone) 913-483-4602

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1110' with 50 sx cement

2nd plug at 510' with 40 sx cement
solid bridge

3rd plug hulls' - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 am Day: 25 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1110' with 50 sx cement, 2nd plug at 510' with 40 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

(do not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 7-30-84

INV. NO. 2759