

1052008

1-23

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-083-20064-0000
C SW SW, SEC. 32, T 23 S, R 21 W/EX

660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30884

Lease Name Gleason B Well # 1

Operator: King Oil Inc.

County Hodgeman 148.36

Name: RR 1

Well Total Depth 4565 feet

Address Jetmore, KS 67854

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 7146

Address Ness City, KS

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 1 Year: 1996

Plugging proposal received from Moe

(company name) Cheyenne Well Service (phone) 913-798-2282

logs: 5 1/2" at 4623', PBSD 4460', Perfs at 4378-86, 4402-4420'

1st plug pump 200 lbs. hulls and 25 sx cement to 4200',

2nd plug perforate 5 1/2" at 600' and pump 200 sx cement down 5 1/2",

3rd plug pump 25 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 23 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement to 4200',

2nd plug perforated 5 1/2" casing at 600' and pumped 200 sx cement down 5 1/2",

3rd plug pumped 25 sx cement down 8 5/8" X 5 1/2" annulus.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
1-30-96
44751
1-23

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED
KANSAS CORP COMM
1996 JAN 28 P 12:18