

1 070545

5-6-88

083-20109-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
SW NW SW, SEC. 32, T 23 S, R 21 W/E  
1650 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Gleason "B" Well # 3

Operator: Pickrell Drilling Company, Inc.  
Name & Address 110 North Market, Suite 205  
Wichita, KS 67202-1996

County Hodgeman 148.75  
Well Total Depth 4577 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 6:45 p.m. Day: 6 Month: 5 Year: 1988

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 4571' PBD 4548' Perfs at 4312-17'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9 p.m. Day: 6 Month: 5 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered approx. 400' of 5 1/2" casing  
(if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas

MAY 13 1988

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (if possible) observe this plugging.

Signed Dan Johnson (TECHNICIAN)

DATE 5-17-88

INV. NO. 20654