

1 050268

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,200-0000  
C SE/2 NW/4 SW/4, SEC. 1, T 18 S, R 20 (H/5)

1650 feet from E/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6732

Lease Name R. Weltmer Well # 002

Operator: VICORP Energy, Inc.

County Rush

Name & Address 6200 S. Syracuse Way, # 125

Well Total Depth 4200 136.50 feet

Englewood, CO 80111

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 552

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 21 Month: June Year: 19 84

Plugging proposal received from Ed Jantz

(company name) H-30 (phone) 316-263-2043

were: \_\_\_\_\_ to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1340' with 50 sx cement

2nd plug at 650' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:45 pm Day: 21 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1340' with 50 sx cement, 2nd plug at 650' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1984  
6-29-84  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Bouie  
(if additional description is necessary, use BACK of this form.)

INVOICED

(check, if not) observe this plugging.

DATE 7-5-84

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 2294