

To: 1 070436
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-7-87
API NUMBER 15- 165-21,382-0000

NW SE NW, SEC. 6, T 18 S, R 20 W/EX
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Pranger Well # 1

Operator: Pintail Petroleum, LTD.
Name & Address 412 East Douglas, Suite One
Wichita, KS 67202

County Rush 137.48

Well Total Depth 4230' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mallard JV Inc. License Number 4958

Address Box 1009, McPherson, KS 67460

Company to plug at: Hour: 10:30 a.m. Day: 7 Month: 10 Year: 19 87

Plugging proposal received from Arnie Hess

(company name) Mallard JV Inc. (phone) 913-731-2869

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2197' Anhydrite 1436-68'

1st plug at 1465' with 50 sx cement, 2nd plug at 700' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 7 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1465' with 50 sx cement,

2nd plug at 700' with 80 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
10-14-87
18498
10-07

Signed Dan Goodnow (TECHNICIAN)

10-13-87
OCT 13 1987
CONSERVATION DIVISION
WICHITA, KANSAS

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 08 22 87 month day year

API Number 15-165-21,382-0000

OPERATOR: License # 5086 Pintail Petroleum, Ltd. 412 E. Douglas, Suite One Wichita, KS 67202 Contact Person: Flip Phillips 316/263-2243

NW SE NW Sec. 6 Twp. 18 S, Rg. 20 3630 998 3630 Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 4958 Mallard JV Inc. McPherson, KS

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 990 feet County: Rush

Well Drilled For: X Oil Storage Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name: Pranger Well # 1 Ground surface elevation 2197 feet MSL Domestic well within 330 feet yes X no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Municipal well within one mile: yes X no Depth to bottom of fresh water 100 Depth to bottom of usable water 600

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date July 30, 1987 Signature of Operator or Agent: Walter James Wheeler Title:

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 300 Conductor pipe required Projected Total Depth 4160 feet Formation: Mississippi

For KCC Use: Conductor Pipe Required Minimum Surface Pipe Required 200 feet per Alt. X (2) This Authorization Expires 1-30-88 Approved By RA 7-30-87

Spud 10/1/87 4:00 has water 300 + 8 1/2

NW SE NW Sec. 6 Twp. 18 S, Rg. 20 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, Formation, Depth to formation, and Plug description. Includes entries for 1st plug @ 50' (Arbuckle), 2nd plug @ 200' (Anhydrite), 3rd plug @ 300' (B/Cheyenne), 4th plug @ 120' (surf-30' below surf pipe), and 5th plug @ 120' (no solid bridge). Includes note (2) Rathole to surface minus 5 feet.

Log table with columns: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ 1465 FT. W/ 50 SX, 2nd PLUG @ 700 FT. W/ 80 SX, 3rd PLUG @ 300 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ 10 SX, WATER WELL PLUGGED W/ 1 SX, CEMENT COMPANY, TECHNICIAN.

RECEIVED STATE CORPORATION COMMISSION OCT 13 1987 10-13-87 CONSERVATION DIVISION Wichita, Kansas

040 670