

1 030761

Plgd. 12-20-86

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2 SE/4 SW/4 SEC. 1, T 18 S, R 20 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,370-0000

660 feet from S section line

3630 feet from E section line

Lease Name Weltmer Well # 1

County Rush 132.02

Well Total Depth 4062 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 510

Operator License # 9067 & 3007

Operator: DaMar Resources, Inc. & Western
Name & Address: Kansas Exploration Inc.
P.O. Box 70
Hays, KS 67601

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling, Inc. License Number 4083

Address Box 126, 2700 Oak, Hays, KS 67601

Company to plug at: Hour: 5 a.m. Day: 20 Month: 12 Year: 19 86

Plugging proposal received from Frank Tigert

(company name) Western Kansas Drilling, Inc. (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2110'
Anhydrite 1336'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 800' with 25 sx cement,

3rd plug at 30' below base of surface pipe with 40 sx cement,

4th plug at 40-0' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7 a.m. Day: 20 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1360' with 50 sx cement,

2nd plug at 800' with 25 sx cement,

3rd plug at 540' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION
12-23-86
DEC 23 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-31-86

Signed Steve Durrant (TECHNICIAN)

INV. NO. 15683
12-20

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 02 86 month day year

API Number 15-165-21,370-0000 East

OPERATOR: License # 9067 3007 Name DaMar Resources, Inc. and Western Kansas Address P. O. Box 70 Hays, KS 67601 Phone (913) 625-0020

W/2 SE/4 SW/4 Sec. 1 Twp. 18 S, Rg. 20 660 Ft. from South Line of Section 3630 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4083 Name Western Kansas Drilling, Inc. City/State Hays, KS

Nearest lease or unit boundary line 660 feet County Rush Lease Name Weltmer Well # 1 Ground surface elevation 2110 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 300' Depth to bottom of usable water 475' Surface pipe planned to be set 500' Projected Total Depth 4000 feet Formation Cherokee/Mississippian

Well Drilled For: X Oil SWD Infield Gas Inj Pool Ext OWWO Expl Well Class: X Mud Rotary Air Rotary Cable Type Equipment: X Wildeat

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing Date 11/24/86 Signature of Operator or Agent Title President

For KCC Use: Conductor Pipe Required 500 feet; Minimum Surface Pipe Required 500 feet per Alt. This Authorization Expires 5-25-87 Approved By 11-25-86

Spud 12-11-86 Set 515'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (feet), Plug depth (feet), Plug depth (feet), Plug depth (feet) and 4 columns: 60/40 poz, 3% gel, 2% c.c. (repeated 4 times)

Table with 2 columns: (a) Rathole with (b) Moushole with. Rows include: 1st PLUG @ 1360 FT. W/ 50 SX, 2nd PLUG @ 900 FT. W/ 25 SX, 3rd PLUG @ 540 FT. W/ 40 SX, 4th PLUG @ 400 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ Hand - SX, CEMENT COMPANY 6/4 67, TECHNICIAN ALLIUS

STATE CORPORATION COMMISSION

DEC 23 1986 12-23-86 CONSERVATION DIVISION Wichita, Kansas