

1 120478
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

-10-9
API NUMBER 15- 165-21,536-0000
SW SW NE, SEC. 1, T 18 S, R 20 W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5815
Operator: C & R Drilling
Name & Address: 410 17th St., #1140
Denver, CO 80202

Lease Name Bryant Well # 1
County Rush 135.49
Well Total Depth 4169 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Mays Drilling License Number 30348
Address P.O. Box 62, Great Bend, KS 67530

Company to plug at: Hour: 10 p.m. Day: 8 Month: 10 Year: 19 90

Plugging proposal received from Mike Mays
(company name) Mays Drilling (phone) 316-792-1255

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1373'
1st plug at 1390' with 50 sx cement, 2nd plug at 700' with 80 sx cement,
3rd plug at 280' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1 a.m. Day: 9 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1390' with 50 sx cement,
2nd plug at 700' with 80 sx cement,
3rd plug at 280' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

10-11-90
OCT 11 1990
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-19-90
INV. NO. 29658

Signed Duan Rankin
(TECHNICIAN)

EFFECTIVE DATE: 10-2-90

State of Kansas

NOTICE OF INTENTION TO DRILL

165-21,536-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: 09/27/90 month day year
SW SW NE Sec 01 Twp 18 S Rg 20 East West

OPERATOR: License # 5815 ✓
Name: C & R DRILLING
Address: 410 17th St. #1140
City/State/Zip: DENVER CO 80202
Contact Person: LES OLSON
Phone: (303) 623-6144
County: RUSH
Lease Name: BRYANT
Field Name: UNKNOWN well# 1

CONTRACTOR: License # 30348 ✓
Name: MAYS DRILLING
Is this a Prorated Field? yes no XX
Target Formation(s): VIOLA
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2145 feet MSL
Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext Air Rotary
 OWWO Disposal Wildcat Cable
 Seismic; # of Holes
Domestic well within 330 feet: yes no XX
Municipal well within one mile: yes no XX
Depth to bottom of fresh water: 350
Depth to bottom of usable water: 550
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 250
Length of Conductor Pipe required: *****
Projected Total Depth: 4250
Formation at Total Depth: ARBUCKLE
Water Source for Drilling Operations: well farm pond other XX
DWR Permit# 1075911990
Will Cores Be Taken? yes no XX
If yes, proposed zone: 10-11-90

Directional, Deviated or Horizontal Wellbore? yes no XX
If yes, total depth location: Exp. 3/27/91
If yes, proposed zone: 10-11-90

The undersigned hereby affirms that the drilling completion and eventual plugging of this well shall be in accordance with the provisions of the Kansas Oil and Gas Conservation Act, Chapter 58, Kansas Statutes Annotated, and the rules and regulations promulgated thereunder.

AFFIDAVIT

Pusher Mike Mays
SPUD DATE 10-1-90 INIT. R.L.C.
LENGTH SURFACE PLANNED 2501
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE CONDUCTOR ELEVATION
SURFACE PIPE 8 3/8 @ 250
ANHYDRITE T- 1379 B-
TD 4169 FORMATION Arb. 41123
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ 504 Ft. W/ 40 SX
Hug./Council @ 1390 Ft. W/ 50 SX
Anhydrite Base @ 200 Ft. W/ 80 SX
1/2 Base Anhy. @ 280 Ft. W/ 40 SX
1/2, 1/2 Plug @ 40 Ft. W/ 10 SX
Bottom Surface @ Ft. W/ SX
40' Plug @ Ft. W/ SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well) Pond Hauling
TECHNICIAN R.L.C. DATE 10-8-90
TYPE OF CEMENT 60/40 port 6% 1/4 # P10500
STARTING TIME 10:00 (AM/PM) DATE 10-8-90
COMPLETION TIME 1:00 (AM/PM) DATE 10-9-90
CEMENT COMPANY Hellbenton
W. F. Newsall - Duane



INVOICE

HALLIBURTON SERVICES

A Halliburton Company

INVOICE NO.	DATE
005891	10/08/1990

WELL LEASE NO./PLANT NAME		WELL/PLANT LOCATION		STATE	WELL/PLANT OWNER	
BRYANT 1		RUSH		KS	SAME	
SERVICE LOCATION		CONTRACTOR	JOB PURPOSE		TICKET DATE	
HAYS		MAYS DRILLING	PLUG TO ABANDON		10/08/1990	
ACCT. NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER		SHIPPED VIA	FILE NO.
131841	DAVE DREILING				COMPANY TRUCK	03148

C & R DRILLING CO
410 17 TH ST SUITE 1140
DENVER, CO 80202

DIRECT CORRESPONDENCE TO:
SUITE 1300
LIBERTY TOWER
100 BROADWAY AVENUE
OKLAHOMA CITY, OK 73102-0000

PRICE REF. NO.	DESCRIPTION	QUANTITY	U/M	UNIT PRICE	AMOUNT
PRICING AREA - MID CONTINENT					
000-117	MILEAGE	38	MI	2.35	89.30
		1	UNT		
090-910	MISCELLANEOUS PUMPING JOB	1	TRK	370.00	370.00
030-503	CMTG PLUG LA-11,CP-1,CP-3, TOP	8 5/8	IN	59.00	59.00
		1	EA		
504-308	STANDARD CEMENT	87	SK	5.45	474.15
506-105	POZHIX A	58	SK	2.88	167.04
506-121	HALLIBURTON-GEL 2%	2	SK	.00	N/C
507-277	HALLIBURTON-GEL BENTONITE	5	SK	13.75	68.75
507-210	FLOCELE	36	LB	1.30	46.80
500-207	BULK SERVICE CHARGE	157	CFT	1.10	172.70
500-306	MILEAGE CMTG MAT DEL OR RETURN	250.914	TMI	.75	188.19
INVOICE SUBTOTAL					1,635.93
DISCOUNT-(BID)					245.36
INVOICE BID AMOUNT					1,390.57
*-KANSAS STATE SALES TAX					56.97
*-HAYS CITY SALES TAX					6.70
INVOICE TOTAL - PLEASE PAY THIS AMOUNT					\$1,454.24

OCT 19 1990
10-19-90

TERMS INVOICES PAYABLE NET BY THE 20TH OF THE FOLLOWING MONTH AFTER DATE OF INVOICE. UPON CUSTOMER'S DEFAULT IN PAYMENT OF CUSTOMER'S ACCOUNT BY THE LAST DAY OF THE MONTH FOLLOWING THE MONTH IN WHICH THE INVOICE IS DATED, CUSTOMER AGREES TO PAY INTEREST THEREON AFTER DEFAULT AT THE HIGHEST LAWFUL CONTRACT RATE APPLICABLE BUT NEVER TO EXCEED 18% PER ANNUM. IN THE EVENT IT BECOMES NECESSARY TO EMPLOY AN ATTORNEY TO ENFORCE COLLECTION OF SAID ACCOUNT, CUSTOMER AGREES TO PAY ALL COLLECTION COSTS AND ATTORNEY FEES IN THE AMOUNT OF 20% OF THE AMOUNT OF THE UNPAID ACCOUNT.