

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-125-02459-0000
 Spot: NESESE Sec 13 Twp 33 S Rng 14 ☒ E / ☐ W
1153 Feet from ☐ N / ☒ S Line of Section
265 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.171050 Long: 95.820420 Date: 2/5/09
 Lease Name: Keith Schill (Stocker) Well #: SCH04
 County: Montgomery Total Vertical Depth: 960 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>12.000</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>PROD - Casing</u>	<u>6.250</u>	<u>960</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____	_____	_____	_____	_____	_____

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 8/5/11 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Fill well with cement from TD to surface.

Plugging Proposal Received By: Tom Bilven Witness Type: PART - Partial
 Date/Time Plugging Completed: 8/5/11 / _____ KCC Agent: Tom Bilven

Actual Plugging Report: _____ Perfs: _____ Top _____ Bottom _____ Thru _____

Run 1" and swedge to 500 ft. Pull out. Perforate at 350, 150 and 75 ft. Run 1" to 950 ft, wash to 960 ft. Pump portland cement from td to surface. Pull pipe and top off well. Pump total of 219 sacks of cement. well plugged.

75 350 TBG - Tubing

KANSAS CORPORATION COMMISSION

OCT 01 2011

RECEIVED

Remarks 20110025-004. PO # 14300-0000000233. Reg. Sec.

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Tom Bilven
(Technician)

Form: District Plugging Report - _____