

5-21

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,518-0000

NE NE NE, SEC. 29, T 18 S, R 20 W/E

4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Reitz Well # 1

Operator: National Cooperative Refinery Assoc.
Name & Address: 1775 Sherman Street, Suite 3000
Denver, CO 80203

County Rush 138.19
Well Total Depth 4252 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8:30 a.m. Day: 21 Month: 5 Year: 19 90

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1329-1365'

1st plug at 1365' with 50 sx cement, 2nd plug at 680' with 80 sx cement,

3rd plug at 385' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Michael R. Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12 p.m. Day: 21 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1365' with 50 sx cement,

2nd plug at 680' with 80 sx cement,

3rd plug at 385' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(additional description is necessary, use BACK of this form.)

(KNOX did not) serve this plugging.

Signed Michael R. Wilson
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DATE 6-5-90
NO. 283
5-21

EFFECTIVE DATE: 5/2/90

State of Kansas

165-21,518-0000

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 5 07 90
month day year

NE. NE. NE. Sec 29. Twp 18. S, Rg 20. X East West

OPERATOR: License # 5565
Name: National Cooperative Refinery Association
Address: 1775 Sherman Street, Suite 3000
City/State/Zip: Denver, CO, 80203
Contact Person: Morris Bell
Phone: (303) 861-4883

4950 feet from South line of Section
330 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: Unknown - will advise on ACO-1
Name: Aperrombas

County: Rush
Lease Name: Reitz Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OMAO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

Target Formation(s): Cherokee
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2080 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 550' 620'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 350'
Length of Conductor pipe required: 0'
Projected Total Depth: 4300'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

If OMAO: old well information as follows:
Operator: N/A
Well Name: _____
Comp. Date: _____ Old Total Depth _____

... well ... farm pond ... other
DWR Permit #: Unknown - will advise
Will Cores Be Taken? yes X no
If yes, proposed zone: _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: _____

Exp. 10/27/90

AFFIDAVIT

280' Alt. IIReq.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Tony Martin
TD 4252 FORMATION Archean light
SURFACE PIPE 891 @ 354 CONDUCTOR
ANHYDRITE T-1329 B-1365 ELEVATION
STARTING TIME 8:30 (AM/PM) DATE 5-21-90
COMPLETION TIME 12:00 (AM/PM) DATE 5-21-90

PLUG NO. 5 Archean Plug @ _____ Ft. W/ SX
4 Archean Plug @ _____ Ft. W/ SX
3 Anhydrite Base @ 1365 Ft. W/ 60 SX
2 1/2 Base Anhyd. @ 680 Ft. W/ 80 SX
1 1/2, 1/2 Plug @ 320 Ft. W/ 2 SX
Bottom Surface @ 385 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ _____ SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY Haliborton

TECHNICIAN _____ DATE _____
TYPE OF CEMENT 60/40 pozzolans W/690
SPUD DATE 5-11-90 INIT. mlw
LENGTH SURFACE PLANNED 350-8 5/8
RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____
no-wee - hand

