

1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,672-0000

SW NE NE, SEC. 33, T 18 S, R 20 W  
4290 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31283

Lease Name Janke Well # 2

Operator: Rheem Resources, Inc.

County Rush

Name & Address 100 S. Main, Ste. 505

Well Total Depth 4300 139.75 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 19 Month: 12 Year: 1994

Plugging proposal received from Richard Wheeler

(company name) Duke Drilling Company Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1460-75'  
1st plug at 1460' with 50 sx cement, 2nd plug at 700' with 80 sx cement,  
3rd plug at 280' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11 a.m. Day: 19 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1460' with 50 sx cement,

2nd plug at 700' with 80 sx cement,

3rd plug at 280' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 28 1994  
12-28-94  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

I ~~did~~ (did not) observe this plugging.

Signed Richard M. Lacey  
(TECHNICIAN)

1-5-95  
41970  
12-19

FOR REC USE:  
EFFECTIVE DATE: 11-22-94  
DISTRICT # 1  
SGA? Yes X No

State of Kansas  
NOTICE OF INTENTION TO DRILL 165-21,672-002

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date November 25 1994  
month day year

Spot SW NE NE Sec 33 Twp 18 S, Rg 20 West

OPERATOR: License # 31283  
Name: Rheem Resources, Inc.  
Address: Suite 505 100 South Main  
City/State/Zip: Wichita, KS 67202  
Contact Person: Clay Hedrick, Jr.  
Phone: 316-262-5099

2970 4,290 feet from South / XXX line of Section  
1538 950 feet from East / XXX line of Section  
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Rush  
Lease Name: Janke Well #: 2  
Field Name: \_\_\_\_\_

CONTRACTOR: License #: 5929  
Name: Duke Drilling Co., Inc.

Is this a Prorated/Spaced Field? .... yes X no  
Target Formation(s): Cherokee Sand  
Nearest lease or unit boundary: .660 feet

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other .....

Ground Surface Elevation: \_\_\_\_\_ feet MSL  
Water well within one-quarter mile: .... yes X no  
Public water supply well within one mile: .... yes X no  
Depth to bottom of fresh water: 420

If OWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Surface Pipe by Alternate: .... 1 (250 - 300) 200' fee  
Length of Surface Pipe Planned to be set: \_\_\_\_\_  
Length of Conductor pipe required: NONE  
Projected Total Depth: 4300

Formation at Total Depth: Cherokee Sand  
Water Source for Drilling Operations:  
... well .... farm pond X other

Directional, Deviated or Horizontal wellbore? .... yes X no  
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_  
Exp. 5/17/95

Will Cores Be Taken?: .... yes X no  
If yes, proposed zone: \_\_\_\_\_

**AFFIDAVIT**

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Clay Hedrick, Richard Wheeler  
SPUD DATE 11-22-94 INIT. CB  
LENGTH SURFACE PLANNED 200'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. \_\_\_\_\_ bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 3/4" @ 24 2/3' CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 1460 B- 1475 ELEVATION \_\_\_\_\_  
TD 4300 FORMATION \_\_\_\_\_  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ SX Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 1460 Ft. W/ 50 SX  
1/2 Base Anyh. @ 700 Ft. W/ 80 SX  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Bottom Surface @ 280 Ft. W/ 40 SX  
40' Plug @ 40 Ft. W/ 40 SX  
RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
TECHNICIAN R. L DATE 12-18-94 Hauling \_\_\_\_\_  
TYPE OF CEMENT 6040 6 1/2" or 1 1/4" C's  
STARTING TIME 12:30 (AM/PM) DATE 12-19  
COMPLETION TIME 11:00 (AM/PM) DATE 12-19-94  
CEMENT COMPANY 400 Allied