

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 50' S NE SW NW, SEC. 33, T 18 S, R 20
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1700 feet from NE section line
990 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444
Operator: Charter Production Company
Name: 224 E. Douglas, Ste. 400
Address: Wichita, KS 67202

Lease Name Frank Well # 1
County Rush
Well Total Depth 4330 - 140.72 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 19 Month: 10 Year: 19 93

Plugging proposal received from Gary

(company name) Duke Drilling Co. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1384-1410'
1st plug at 1450' with 50 sx cement, 2nd plug at 600' with 50 sx cement,
3rd plug at 300' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 a.m. Day: 19 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,

2nd plug at 600' with 50 sx cement,
3rd plug at 300' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1993
10-28-93
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

(XXX) did not observe this plugging.

39058
10-19

Signed Case Morris (TECHNICIAN)

EFFECTIVE DATE: 10-13-93

DISTRICT # 1

SCAT Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL

165-21,643-002

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10-9-93
month day year

50' Spnt S. NE. SW. NW. Sec. 33. Twp 18. S. Rg 20. East West

OPERATOR: License # 30444 ✓
Name: CHARTER PRODUCTION COMPANY
Address: 224 E. Douglas, Suite 400
City/State/Zip: Wichita, Kansas 67202
Contact Person: Jerald W. Rains
Phone: 316-264-2808

1700' feet from ~~XXXX~~ North line of Section
990' feet from ~~XXXX~~ West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: RUSH
Lease Name: FRANK Well #: 1
Field Name:

CONTRACTOR: License #: 5929 ✓
Name: Duke Drilling Co.

Is this a Prorated/Spaced Field? yes X no ✓
Target Formation(s): Cherokee/Mississippi
Nearest lease or unit boundary: 990'
Ground Surface Elevation: 2139' feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X. Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OWS ... Disposal X Wildcat ... Cable
... Seismic: ... # of Holes ... Other

Water well within one-quarter mile: yes X no ✓
Public water supply well within one mile: yes X no ✓
Depth to bottom of fresh water: 420' ✓
Depth to bottom of usable water: 440' ✓

Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: (360?) 200'
Length of Conductor pipe required: NA
Projected Total Depth: 4250'
Formation at Total Depth: Mississippi

Directional, Deviated or Horizontal wellbore? yes X no
Bottom Hole Location Exp. 4/8/94

Water Source for Drilling Operations: well X farm pond other
Oil Permit #: ...
Will Cores Be Taken?: yes X no ✓
If yes, proposed zone:

AFFIDAVIT

200' Alt. II Req.

I, the undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-11, et. seq.
It is agreed that the following minimum requirements will be met.

Pusher Gary

SPUD DATE 10-11-93 INIT. *rw*

LENGTH SURFACE PLANNED 250'-8 5/8

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 256 CONDUCTOR
ANHYDRITE T- 224 B- 1410 ELEVATION

TD 4250 FORMATION

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1450 Ft. W/ 50 SX

1/2 Base Anyh. @ 600 Ft. W/ 50 SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 300 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN CM DATE 10-18-93

TYPE OF CEMENT 60/40 670

STARTING TIME 3:00 (AM/PM) DATE 10-11-93

COMPLETION TIME 5:30 (AM/PM) DATE 10-19-93

CEMENT 203

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1993
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1993
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1993
WICHITA, KANSAS