

1-040451

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,226-0000 *R*N/2 SE/4, ^{NW/4} SEC. 20 ; T. 19 S, R. 17 *W* *X*1650 feet from N/~~W~~ section line1980 feet from W/~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9645

Lease Name William Well # 1

Operator: Beasley Oil Company

County Rush

Name & Address 4301 N.W. 63rd, Suite 304

Well Total Depth 3955 128.54 feet

Oklahoma City, OK 73116

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well Gas Well Input Well SWD Well D&A *X*

Other well as hereinafter indicated

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 1:00 am Day: 27 Month: June Year: 19 84

Plugging proposal received from Jim Ray

(company name) DaMac (phone) 316-792-1353

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3920' with 50 sx cement

2nd plug at 1230' with 50 sx cement

3rd plug at 500' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by *Paul A. Luthie* (TECHNICIAN)Plugging Operations attended by Agent?: All Part None *X*

Operations Completed: Hour: 10:30 am Day: 27 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3920' with 50 sx cement, 2nd plug at 1230' with 50 sx

cement, 3rd plug at 500' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx

cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1984

7-6-84

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed *Paul A. Luthie* (TECHNICIAN)7-16-84
2484
6-27