

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,333-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 7261

Operator: Pate - Dombaugh Petroleum
Name & Address 922 Union Center Bldg
Wichita, KS 67202

4950 feet from S section line

2970 feet from E section line

Lease Name Raup Well # 1

County Rush 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 473

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor B + B Drilling Co. License Number 5110

Address 501 Union Center Wichita 67202

Company to plug at: Hour: 9:00 pm Day: 8 Month: November Year: 1985

Plugging proposal received from John Armbruster

(company name) B + B Drilling Co. (phone) 316-267-0613

Work: keep hole full of heavy mud + spot cement plugs
through drill pipe. 1st plug @ base of the Anhydrite
with 50sx, 2nd plug @ 500' with 40sx, 3rd
plug @ 40' with a solid Bridge Plug + 10sx of cement
Circulate 15sx in the rat hole

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pm Day: 8 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy mud + spotted
cement plugs through drill pipe. 1st plug @ 1230' w/50sx
2nd plug @ 500' w/40sx
3rd plug @ 40' w/SBP + 10sx

Circulate Rathole with 15sx of cement
Anhydrite @ 1200' Elevation 2110' GL

Remarks: Allied Cementing pumped 60/40 pozmix 6% gel cement
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
I (state/did not) observe this Commission.

NOV 22 1985

NOV 18 1985

Signed Richard W. Lacey
(TECHNICIAN)

DATE NOV 22 1985

NOV 22 1985

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84