

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bldg., Wichita, Kansas 67202

Lease Name Brannan Well No. 1

Location NE NE NE Sec. 22 Twp. 19 Rge. (E) (W) 17

County Rush Total Depth 4000

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 12:15P Day 18 Month 12 Year 1969

The above well was plugged as follows:

RTD 4000 8 5/8 csg set at 268' cwc Cmt. Mat. 50-50 poz cmt 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Leo J. Massey  
Well Plugging Supervisor

12/19/69  
1089-W