

15-165-20281-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
DEC 31 1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bldg., Wichita, Kansas

Lease Name Schraeder "B" Well No. 1

Location NW SW Sec. 18 Twp. 19 Rge. (E) (W) 17

County Rush Total Depth 4002

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 2 A Day 29 Month 12 Year 1969

The above well was plugged as follows:

RTD 4002' 8 5/8 csg set at 272' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

*Handwritten notes:*  
12/31/69  
1183-W