

District Plugging Report

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>Surf</u>	<u>8</u>		<u>0</u>	
Address 1: <u>130 S MARKET</u>	<u>Prod</u>	<u>2.875</u>		<u>0</u>	
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: Oil UIC Docket No.: _____ Date/Time to Plug: _____ / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE
 Proposal Rcvd from: JEFF FREDERICKS (RAMBO) Company Name: _____ Phone: (620) 433-7196

Proposed Plugging Report:

CLEAN WELL TO BOTTOM. PUMP FULL OF PORTLAND CEMENT INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS THE CASING SHOULD BE PERFERD IN AT LEAST 2 INTERVALS, UNLESS DOCUMENTED AN ALT2 COMPLETION.

Plugging Proposal Received By: TOM BILYEU Witness Type: PART - Partial
Date/Time Plugging Completed: 4/2/12 / _____ KCC Agent: TOM BILYEU
Actual Plugging Report: _____ Perfs: Top Bottom Thru

PREF 2.875" PIPE AT 350', 150' AND 75'. RAN 1" PIPE TO 1125' PUMPED CEMENT TO SURFACE. USED 105 SACKS CEMENT.

KANSAS CORPORATION COMMISSION
OCT 02 2012
RECEIVED

Remarks	CONTRACT#EVT0000981; CONTROL#20120009-016 ; NAD27
---------	---

Abandoned Well Database Shows INT Well

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No**District: 03**

Thomas B. Byers
(Technician)

Form: District Plugging Report –