



15-025-00108-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Bovaird Supply Co. has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Co.

Complete Address: Box 358, Liberal, Kansas

Lease Name: Daisy Wall Well No. 1

Location: 1980' ^{CNE SE} ~~1980'~~ ^{N of St} & ~~660'~~ ^{E of Wk} Sec. 35 Twp. 32 Rge. 23 (E)(W)

County Clark Total Depth 6859' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargents was instructed to plug the well as follows:

13 3/8" to 525' circulated w/ cement. 9 5/8" to 2510' ciru. W/ cement.

5 1/2" to 6818' cemented. Top perforations 4476'

Plug bottom w/ 15 sacks cement Top of cement 4300'

Mud 4300' to 700' Spotted 40 sacks cement 700' to 600'

Mud 600' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent