

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-055-20001-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 8 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Richter of Helmerich & Payne has this

date requested permission to plug the following described well:

Mr. Richter guarantees payment of the plugging fee.

Operator's full Name: Helmerich & Payne, Inc.

Complete Address: Box 558, Garden City, Kansas 67846

Lease Name: Wagner "A" Well No. 1

Location: C SE SE Sec. 7 Twp. 25 Rge. 34 XX (W)

County Finney Total Depth 5172' Oil Well X

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Richter was instructed to plug the well as follows:

8 5/8" to 815' circulated w/ cement. 5 1/2" to 5168' cemented.

Top perforations 4125' Plug Bottom w/ 15 sacks cement.

Top of cement 4000' Mud 4000' to 700'

Spotted 40 sacks cement 700' to 600' Mud 600' to 35'

Plug, Halls & 10 sacks cement 35' to 0'

Very truly yours,

Edgar J. Evers
Conservation Division Agent