



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Shively of Hartman has this
date requested permission to plug the following described well:

Mr. Shively guarantees payment of the plugging fee.

Operator's full Name: W.L. Hartman

Complete Address: Box 54, Wichita, Kansas

Lease Name: Pritchett Well No. 2

Location: C SE NW Sec. 4 Twp. 22 Rge. 33 ~~(E)~~ (W)


County: Finney Total Depth 4850' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shively was instructed to plug the well as follows:

- 8 5/8" to 336' circulated w/ cement. Mud 4850' to 2900'
- Spot 100 Sacks cement 2900' to 2600' Mud 2600' to 700'
- Spot 35 sacks cement 700' to 600' Mud 600' to 300'
- Spot 35 sacks cement 300' to 200' Mud 200' to 45'
- Plug, Mulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent