



15-129-00126-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1965
03-16-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Barnard of Pan American Pet.Corp. has this date requested permission to plug the following described well:

Mr. Barnard guarantees payment of the plugging fee.

Operator's full Name: Pan American Pet.Copr.

Complete Address: Box 432 Liberal, Kansas

Lease Name: Bear Gas Unit A Well No. # 1

Location: NW NW SE Sec. 17 Twp. 32 Rge. 40 (E) (W)

County Morton Total Depth 6561' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Barnard was instructed to plug the well as follows:

8 5/8"-2397' Circulated w/cement. 5 1/2"-5059' Circulated w/cement.


Plug back to 5036' Plug bottom w/20 Sax.cement top cement 4460'

Mud 4460' to 2325' Spotted 20 "as.cement 2325' to 2220'

Mud 2220' to 810' Spotted 30 Sax.cement 810' to 700'

Mud 700' to 90' Spotted 30 Sax.cement 90' to 0

Very truly yours,


Conservation Division Agent