

1080243

TO: STATE CORPORATION COMMISSION

2-26

API NUMBER 15-055-20,477 0050
C NW NE SEC. 3, T 22 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ANDERSON WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY

OPERATOR LICENSE # 100 101 ^{ANS} _{CC}

WELL TOTAL DEPTH 4291 FEET

OPERATOR: KCC FEE FUND #990066-002

PRODUCTION CSG: SIZE 5 1/2" @ 4291' WITH NA SX

NAME AND 130 S MARKET RM 2078

SURFACE CASING: SIZE 8 5/8" @ 880' WITH NA SX ^{circulated to surface}

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31, RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 26 MONTH: 02 YEAR: 1999
1:15 PM DAY: 26 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KEVIN STRUBE

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 2610'-2650'

PUMP DOWN 5 1/2" CASING WITH 500# HULLS AND 266 SX CEMENT. CUT OFF CASING AND RESTORE

LOCATION.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 26 MONTH: 02 YEAR: 1999
HOUR: 2:00 PM DAY: 26 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT

ALLIED PUMPED DOWN 5 1/2" CASING 300# HULLS WITH 200# HULLS MIXED IN FIRST PART OF CEMENT,

PUMPED 260 SX CEMENT NO PRESSURE SHUT IN. TOPPED OFF WITH 50 SX CEMENT AFTER LETTING SET

2 HOURS. HOLE STAYED LOADED. CHECK ANNULAS 8 5/8" X 5 1/2" 500# PRESSURE.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube
(TECHNICIAN) FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1999

Wichita, Kansas

RAWZ