

1-100033

194 R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
WICHITA STATE OFFICE BUILDING  
WICHITA, KANSAS 67202

API number: 15-129-20,945 ~~0000~~  
APP. SE SW SEC. 17, 32 S, 40 W  
660 feet from S section line  
3275 feet from E section line

Operator license# 5363

Lease Hutton well # 1

Operator: BEREXCO INC.

County Morton

Address: P.O. Box 723

Well total depth 5620 feet

HAYS, KS 67601

Conductor Pipe: inch @ feet

Surface pipe: 8 5/8 inch @ 1630 feet

182.65-

Aband. Oil well \_\_, Gas well X, Input well \_\_, SWD \_\_, D & A \_\_

Plugging contractor: Sargent & Horton Plugging Service License# 31151

Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10:00 a.m. Day: 27 Month: March Year: 1996

Plugging proposal received from: Don Horton

Company: Sargent & Horton Plugging Service Phone: 405-854-6515

Were: 4 1/2" at 5620' w/500 sx cement, PBTB 5562', Perfs at 5503-07', 5432-47'

Multi-stage collar at 2960' w/550 sx cement, CIBP at 5490', TOC 3425'

1st plug pump 20 sx cement and 2 sx hulls on bottom.

2nd plug pump 50 sx cement on stub,

3rd plug pump 50 sx cement at 1660',

4th plug pump 40 sx cement at 700',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by: Richard Lacey

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 1:00 p.m. Day: 27 Month: March Year: 1996

Actual plugging report:

1st plug set 20 sx cement and 2 sx hulls from 5432-5232.

2nd plug free point at 627', circulated hole and set a 50 sx plug.

3rd plug pulled to 40' and set 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 627' of 4 1/2" casing.

I did[X] / did not[ ] observe the plugging.

Ray Runtz  
(agent)

Form CP-2/3

*[Handwritten initials]*

INVOICED

4-10-96

45172

3-27

RECEIVED  
KANSAS CORP COMM  
1996 APR -1 A 10:42