

1052363

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED 03/07/62 15-165-19001-00-00
C N/2 S/2 SEC. 13, T 17 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ERNI WELL # 1

TECHNICIAN'S PLUGGING REPORT

12/30

COUNTY RUSH 109.36

OPERATOR LICENSE # 3842

WELL TOTAL DEPTH 3365 FEET

OPERATOR: LARSON OPERATING COMPANY PRODUCTION CSG: SIZE 2 7/8" @ 3170' WITH SX

NAME AND 562 W HIGHWAY 4 SURFACE CASING: SIZE 8 5/8" @ 348' WITH 200 SX

ADDRESS OLMITZ, KS 67564-8561

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 30 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TED FUCHS

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: PERFS AT 3047-3053 8 5/8" X 2 7/8" ANNULUS CEMENTED FROM 1124-0 THROUGH 1 1/4" TUBING THAT WAS LEFT IN HOLE.

PUMPED 10 SX CEMENT DOWN 8 5/8" X 2 7/8" ANNULUS. PUMPED 800# HULLS AND 210 SX CEMENT DOWN 2 7/8" TUBING. MAXIMUM PRESSURE AT 1000 PSI. SHUT IN WITH 500 PSI.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:46 PM DAY: 30 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED 10 SX CEMENT DOWN 8 5/8" X 2 7/8" ANNULUS. PUMPED 800# HULLS AND 210 SX CEMENT DOWN 2 7/8" TUBING. MAXIMUM PRESSURE AT 1000 PSI. SHUT IN WITH 500 PSI.

RECEIVED STATE CORPORATION COMMISSION

JAN 10 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERY. CONSERVATION DIVISION
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

Put on Feb. report

Handwritten initials and a circled 'R'.