

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20478-00-01
Spot: CNE Sec/Twnshp/Rge: 17-17S-17W
3960 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: DAUBERT Well Number: 1
County: RUSH Total Vertical Depth: 3627 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 213 WITH 170 SX CMT
Production: Size 4.5 feet: 3527 WITH 100 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/21/2003 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KCC Phone: (620) 225-8888

Proposed Plugging Method: PULL TUBING STRING. PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX COMMON CMT. DISPLACE TO 3000'. FREEPOINT & RECOVER 4 1/2" CASING. PULL CASING TO 1220' & SPOT 10 SX GEL & 50 SX CMT. PULL CASING TO 500' 7 SPOT 50 SX CMT. PULL CASING TO 240' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 10 SX CMT. RESTORE LOCATION.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/21/2003 10:20 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3382-95 & 3136-47'. TUBING FISH @ 485' TO 3000'. MANY ATTEMPTS WERE MADE TO FISH OUT TUBING. MILLED OUTSIDE OF CASING TO 523'. RAN TUBING TO 522'. PUMPED 110 SX CMT DOWN TUBING CIRCULATING CMT TO SURFACE UP 4 1/2' & 8 5/8" X 4 1/2" ANNULUS. LAID DOWN TUBING. PRESSURE 4 1/2" & 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH 10 SX CMT. SHUT IN PRESSURE 300 PSIG.

RECEIVED
JAN 28 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)