

To: 10-14
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 3447

Operator: Ranken Energy Corporation
Name & Address: 601 N. Kelly, Ste. 103
Edmond, OK 73038-4855

API NUMBER 15-135-24,032-00-00
SW SW NW, SEC. 27, T. 20 S, R. 26 W
2970 feet from S section line
330 feet from WE section line

Lease Name Blakely Well # 1-27
County Ness 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Discovery Drilling, Inc. License Number 31548
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 2:30 p.m. Day: 14 Month: 10 Year: 1997

Plugging proposal received from Tom Alm
(company name) Discovery Drilling, Inc. (phone) 785-623-2920

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1710-47'
1st plug at 1750' with 50 sx cement, 2nd plug at 900' with 80 sx cement,
3rd plug at 250' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:15 p.m. Day: 14 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1750' with 50 sx cement,
2nd plug at 900' with 80 sx cement,
3rd plug at 250' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

I (XXXX) / did not observe this plugging.
Signed _____ (TECHNICIAN)

49290
10-14

State of Kansas

EFFECTIVE DATE: 9-22-97

NOTICE OF INTENTION TO DRILL 15 135-24,032 00-00 BLANKS MUST BE FILLED

DISTRICT # 1

SCA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 9 month 25 day 97 year

Spot SW/4 - SW/4 - NW/4 Sec 27 Twp 20 S, Rg 26 West East

OPERATOR: License # 3447
Name: RANKEN ENERGY CORPORATION
Address: 601 N. Kelly, Ste. 103
City/State/Zip: Edmond, OK 730038-4855
Contact Person: Tom Larson
Phone: 316/653-7368

CONTRACTOR: License #: 31548
Name: DISCOVERY DRILLING, INC.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ... X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal ... X Wildcat ... Cable
... Seismic; ... # of Holes ... Other ... Exp. 3/17/98
... Other

If OWWO: old well information as follows:

Operator: N/A

2970 feet from South North line of Section
330 feet from East West line of Section

IS SECTION REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Ness

Lease Name: Blakely Well #: 1-27

Field Name: Wildcat

Is this a Prorated/Spaced Field? ... yes no

Target Formation(s): Mississippian

Nearest lease or unit boundary: 330

Ground Surface Elevation: 2428 Est. feet MSL

Water well within one-quarter mile: ... yes no

Public water supply well within one mile: ... yes no

Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 900'

Surface Pipe by Alternate: ... 1 2 200' Alt. II

Length of Surface Pipe Planned to be set: 200' Req.

Length of Conductor pipe required: N/A

Projected Total Depth: 4525'

Formation at Total Depth: Mississippian

10-17-1997

Pusher Tom
SPUD DATE 10-6-97 INIT. SA
LENGTH SURFACE PLANNED 200'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 222.07 CONDUCTOR
ANHYDRITE T- 1710 B- 1747 ELEVATION 2970 GL

TD 4550 FORMATION M155

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1750 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

2 1/2, 1/2 Plug @ 900 Ft. W/ 80 SX

3 Bottom Surface @ 250 Ft. W/ 40 SX

4 40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL NO SX (Irr. Well Fond)

TECHNICIAN SA DATE 10-13-97 Hauling

TYPE OF CEMENT 60/40 Poz 6% G 44

STARTING TIME 2:30 (AM/PM) DATE 10-14-97

COMPLETION TIME 4:15 (AM/PM) DATE 10-14-97

CEMENT COMPANY ACCIED