

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 165-20,547-0000
SE NW SW, SEC. 30, T 17 S, R 16 W/E
1650 feet from S section line
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456
Operator: AFG Energy Inc.
Name & Address: P.O. Box 458
Hays, KS 67601

Lease Name Rothe A Well # 1
County Rush
Well Total Depth 3508 114.01 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, KS

Company to plug at: Hour: 10:30 a.m. Day: 11 Month: 3 Year: 1996

Plugging proposal received from Terry W. Piesker

(company name) AFG Energy Inc. (phone) 913-625-6374

were: 4 1/2" at 3506' w/275 sx cement, PBSD 3464', Perfs at 2982-3450', DV @ 1105' w/550 sx.cmt.

1st plug pump 500 lbs. hulls and fill with cement.

RECEIVED
KANSAS CORP. DIV.
MAR 11 1996

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 11 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 500 lbs. hulls and 200 sx cement.

Pumping pressure 0-1000 psi and shut in 800 psi.

Cement in braden head.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I did / ~~did not~~ observe this plugging.

Signed Dustin Rankin (TECHNICIAN)

45091