

15-TGS-00072-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
10-2-62
OCT 2 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drg Co

Complete Address: 313 1st Natl Bk Bldg Wichita, Kansas

Lease Name Lohrey Well No. 1

Location SW SW SW Sec. 35 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3606

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Kent Well Service

Address: El Dorado, Kansas License No. 394

Operation Completed: Hour 7PM Day 27 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 107 1/2' circulated with cement - 5 1/2" 3605' with 125 sax cement -
perforated 3563' - filled with sand to 3550', set 5 sax cement with dump
bailer - pulled 2800' 5 1/2" to 420' - tried to circulate mud - hole pressured
up - pulled pipe to 370' - circulated hole with heavy mud (33 sax Gel),
displaced 20 sax cement through 5 1/2" at 370', heavy mud to 165', displaced
20 sax cement through 5 1/2" at 165', heavy mud to 35', cement 35' to bottom
cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Kelly
Well Plugging Supervisor

DATE 10/3/62
INV. NO. 5795-W