



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Et Al, Inc.

Complete Address 119 Cameran Bldg., Oklahoma City, Oklahoma 73106

Lease Name Lohrey Well No. 1

Location SE SE NE Sec. 34 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3582'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 10 A Day 3 Month 6 Year 1975

The above well was plugged as follows:

Total Depth 3582' 8 3/8 csg set 1097' cwc 500 sk.

4 1/2 csg set 3581' cw 75 sk cem.

4 1/2 csg PBD 3550' with top perf. (3543')

Filled 4 1/2 csg W/sd (3550-3500) dumped 4 sk cem W/dump bailer. (3500-3465)

Cutoff & recovered 3010' of 4 1/2 csg.

Drilling mud to 350' -set rock & sand bridge (350-325)

Filled with readymix cem. from 325' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Menden
Well Plugging Supervisor

INVOICED

DATE 6/9/75

INV. NO. 1449-w